

## ANNEX A. SCOPE OF WORKS

### Scope of Works

Suppliers/Bidders should indicate "COMPLY" or "NOT COMPLY" to the specifications/requirements below.

#### CONSTRUCTION OF CONCRETE PLATFORM AT SSS CEBU BRANCH

Item	Specification	Statement of Compliance
I	<p>SCOPE OF WORK</p> <p>The work contemplated under this contract shall consist of the furnishing of all materials, labor, tools and equipment, work permits including the satisfactory performance of all works necessary for the complete execution of all the work as shown on the plans, specifications and other contract documents.</p> <p>1. MOBILIZATION</p> <p>2. SITE PREPARATION</p> <p style="padding-left: 20px;">2.1 Closure &amp; Isolation of Working Area</p> <p style="padding-left: 20px;">2.2 Clearing of Area</p> <p style="padding-left: 20px;">2.3 Excavation Works</p> <p style="padding-left: 20px;">2.4 Hauling and disposal of debris and waste materials</p> <p>3. CONCRETING &amp; MASONRY WORKS</p> <p style="padding-left: 20px;">3.1 Concreting of Foundation (Wall Footing &amp; Columns) &amp; Concrete Floor</p> <p style="padding-left: 40px;">Cement - Portland</p> <p style="padding-left: 40px;">Sand - Good Quality Sand</p> <p style="padding-left: 40px;">Gravel - Good Quality Gravel</p> <p style="padding-left: 40px;">Concrete Mixture - Class "A", 1:2:4</p> <p style="padding-left: 40px;">Concrete Strength - 2,500 psi (minimum)</p> <p style="padding-left: 20px;">3.2 CHB Laying &amp; Plastering</p> <p style="padding-left: 40px;">Cement - Pozzolan / Masonry</p> <p style="padding-left: 40px;">Sand - Good Quality Sand</p> <p style="padding-left: 40px;">CHB Size - 150mm x 200mm x 400mm</p> <p style="padding-left: 40px;">Mortar Mixture - Class "B", 1:3</p> <p style="padding-left: 40px;">Plastering Mixture - Class "A", 1:2</p> <p style="padding-left: 20px;">3.3 Installation of Reinforcing Bars</p> <p style="padding-left: 40px;">Reinforcing Bars - ASTM Grade 40</p> <p style="padding-left: 40px;">Tie Wire - G.I. Tie Wire No. 16</p> <p>4. BACKFILLING</p> <p style="padding-left: 20px;">2.1 Sub-Base - Good Quality Anapog</p> <p style="padding-left: 20px;">2.2 Base-Course - Good Quality Gravel</p> <p>5. CARPENTRY WORKS</p> <p style="padding-left: 20px;">4.1 Scaffolding - Good Quality Coco Lumber or G.I. Pipe</p> <p style="padding-left: 20px;">4.2 Forms - Marine Plywood, 1/2" thick</p>	

II	WORKMANSHIP	All required phases of work shall be done by skilled and competent men who regularly engage or specialize in the type of work specified. Workmanship shall be the very best trade practice.	
III	SITE EXAMINATION	Examine the site premises and all conditions apparent and visible therein. Consider all such conditions that may affect work.  Measure every existing work/structure at site. Verify all given dimensions and deviations. It shall be understood that the work covers all exposed external surfaces regardless of measurements made.	
IV	PROTECTION OF WORK AND PROPERTY	Provide adequate protection for existing structures and other areas not affected by the work specified and the ground below. Place warning signs where work is being undertaken.  Remove work materials damaged by failure to provide protection. Replace with new work materials at no extra cost to the OWNER.	
V	CLEANING	Leave premises clean, neat and orderly. Remove all stains, spots, blemishes, soil dirt from all finished work.  Remove all excess materials, used containers, tools, equipment and supplies out of the SSS premises during the progress upon completion of work.	
VI	WORK HOURS	Weekdays: 7:00 AM – 5:00 PM 5:00 PM onwards (works which generate intolerable disturbances like noise and odor) Weekends/Holiday: 8:00 AM onwards	
VII	DELIVERY TERMS	Delivery terms of Thirty Five (35) calendar days upon receipt of approved JO/PO	

*Almira R. Estavilla*

**ALMIRA R. ESTAVILLA**

Owner/Authorized Representative  
(Signature Over Printed Name)