

**PROJECT: PREVENTIVE MAINTENANCE OF SEWERAGE TREATMENT PLANT AT HONG KONG SUN PLAZA PROPERTY (3<sup>RD</sup> ADVERTISEMENT)**

**QUERIES/CLARIFICATIONS RAISED DURING THE PRE-BID CONFERENCE:**

	<b>Query/Clarifications</b>	<b>TWG/BAC Reply</b>
1	What is the system of our Sewerage Treatment Plant (STP)?	Our system is a Sequencing Batch Reactor (SBR). After the SBR, we have added an Electro Contaminant Remover (ECR) equipment to enhance the quality of our effluent.
2	How many cubic meters per day is the SBR?	It is designed to process 400 cubic meters.
3	Is it already compliant with 2016-08?	Yes.
4	Is it possible if we could ask for a Sewerage Treatment Plant as-built (STP) and Sample Test Result (STR)?	Yes. The bidder will be provided with Sewerage Treatment Plant (STP) as-built plans and Sample Test Result (STR)
5	Can you e-mail it to all the bidders?	Yes. It will be issued together with the bid bulletin.
6	What is the daily flow rate?	It averages from 40 to 80 cu/m per day.
7	For the disposal of the sludge waste, will you be in-charge of the hauling of the disposal including the siphoning?	The service provider will do the hauling and siphoning.
8	You mentioned that the operator is 8 hours per day/shift, 7 days a week, how about for the succeeding hours?	Yes. With the operators, we require three (3) operators working in shifts. The service provider will provide for the 3 operators. If ever one of the employees is not able to come in as scheduled, it will be deducted on the payment. If the service provider will have their personnel render for 12 hours, we will only pay for 8hrs.
	Is it 24/7?	Yes.