## **Scope of Works**

Suppliers/Bidders should indicate "COMPLY" or "NOT COMPLY" to the specifications/requirements below.

## SUPPLY OF MATERIALS AND LABOR FOR THE INSTALLATION OF FLOOR TILES AT SSS TALISAY BRANCH

Item I	Specification		Statement of Compliance
	SCOPE OF WORK	The work contemplated under this contract shall consist of the furnishing of all materials, labor, tools and equipment, work permits including the satisfactory performance of all works necessary for the complete execution of all the work as shown on the plans, specifications and other contract documents.	
		1. MOBILIZATION / DEMOBILIZATION	
		SITE PREPARATION     Closure & Isolation of Working Area     Removal of Damaged Tiles     Moving of Affected Furniture & Other Items     Hauling and disposal of debris and waste materials	
		3.ARCHITECTURAL WORKS / TILEWORKS 3.1 Installation of Porcelein Tiles, 600mm x 600mm using heavy duty tile adhesive as bonding component	
II	WORKMANSHIP	All required phases of work shall be done by skilled and competent men who regularly engage or specialize in the type of work specified. Workmanship shall be the very best trade practice.	
111	SITE EXAMINATION	Examine the site premises and all conditions apparent and visible therein. Consider all such conditions that may affect work.  Measure every existing work/structure at site. Verify all given dimensions and deviations. It shall be understood that the work covers all exposed external surfaces regardless of measurements made.	
IV	PROTECTION OF WORK AND PROPERTY	Provide adequate protection for existing structures and other areas not affected by the work specified and the ground below. Place warning signs where work is being undertaken.  Remove work materials damaged by failure to provide protection. Replace with new work materials at no extra cost to the OWNER.	
V	CLEANING	Leave premises clean, neat and orderly. Remove all stains, spots, blemishes, soil dirt from all finished work.	
		Remove all excess materials, used containers, tools, equipment and supplies out of the SSS premises during the progress upon completion of work.	

VI	WORK HOURS	Weekdays: 9:00 AM – 5:00 PM Weekends - works which generate intolerable disturbances like noise and odor Weekends/Holiday: 9:00 AM onwards	
VII	DELIVERY TERMS	Delivery terms of sixty (60) calendar days upon receipt of approved JO/PO	

MICHELLE ROFE LOVE BAYALAS
Owner/Authorized Representative
(Signature Over Printed Name)