



Republic of the Philippines
SOCIAL SECURITY SYSTEM
LUZON CENTRAL 2 DIVISION
 SSS Bldg., Diosdado Macapagal Government Center
 Brgy. Maimpis, City of San Fernando, Pampanga

PROJECT : REPAINTING OF SSS PAMPANGA BRANCH
LOCATION : DMGC, Brgy. Maimpis, City Of San Fernando, Pampanga
SUBJECT : BILL OF QUANTITIES

ITEM NO.	DESCRIPTION	QTY.	UNIT	MATERIALS		LABOR & EQUIPMENT		DIRECT COST	MOB./ DEMOV.	MARK UP	VAT	TOTAL COST
				Unit Cost	Amount	Unit Cost	Amount					
(A)	(B)	(C)	(D)	(E)	(F) Cx E	(G)	(H) Cx G	(I) F + H	(J) 1% x (F + H)	(K) 25% x (I+J)	(L) 12% x (I+J + K)	(M) I + J + K + L
I	SITE PREPARATION											
	1. Temporary Facilities and Board-Up /Enclosure, Safety & Protective Signages	1	lot	-	-	-	-	-	-	-	-	-
	2. Installation and erection of temporary Scaffolding	1	lot	-	-	-	-	-	-	-	-	-
	3. Preparation of wall surfaces removal/chipping of all loose/flaking old paints	1	lot	-	-	-	-	-	-	-	-	-
	4. Preparation of metal surfaces removal of all rusted portion of metal	1	lot	-	-	-	-	-	-	-	-	-
	5. Hauling & Disposal of Debris & waste materials	1	lot	-	-	-	-	-	-	-	-	-
	TOTAL COST - SITE PREPARATION											-
V	DOORS											
	1 SERVICE DOOR REPLACEMENT											
	1.1 WOOD DOOR 01	1	set/s	-	-	-	-	-	-	-	-	-
	1000mmX2100mm Panel Wood Door with LeverType Lockset, Dead Bolt , Stainless Steel Hinges with Bearings, 2"X6" Tanguile Door Jamb KD, Complete with Hardware and Accessories.											
	1.2 Door Closer with built-in hold open function	1	set/s	-	-	-	-	-	-	-	-	-
	2 GLASS DOOR REPAIR (Main Entrance)											
	2.1 Repair of Glass Door (replacement defective door handle & other necessary fitting, lockset and accessories)	1	lot	-	-	-	-	-	-	-	-	-
	TOTAL COST - DOORS											-
VI	PAINTING WORKS											
	1. Exterior and Interior Wall											
	1.1 Elastomeric Primer	2	tin/s	-	-	-	-	-	-	-	-	-
	1.2 Dirt Shield Elastomeric Semi-Gloss	9	tin/s	-	-	-	-	-	-	-	-	-
	1.3 Primer Latex	1	tin/s	-	-	-	-	-	-	-	-	-
	1.4 Semi-Gloss Latex (Ready mix)	5	tin/s	-	-	-	-	-	-	-	-	-
	2. Ceiling (Fiber Cement Board) and Door & Jamb											
	2.1 Flat Wall Enamel	6	gal/s	-	-	-	-	-	-	-	-	-
	2.2 Wood/Timber Primer	2	gal/s	-	-	-	-	-	-	-	-	-
	2.3 Water Base Quick Dry Enamel (Aqua Gloss-it)	3	gal/s	-	-	-	-	-	-	-	-	-
	3. Roof Sheeting & Spandrel Ceiling											
	3.1 Roof Paint	7	tin/s	-	-	-	-	-	-	-	-	-
	3.2 Metal Primer	1	gal/s	-	-	-	-	-	-	-	-	-
	3.3 Waterproofing Sealer	5	ltr/s	-	-	-	-	-	-	-	-	-

ITEM NO.	DESCRIPTION	QTY.	UNIT	MATERIALS		LABOR & EQUIPMENT		DIRECT COST	MOB./ DEMOV.	MARK UP	VAT	TOTAL COST
				Unit Cost	Amount	Unit Cost	Amount					
(A)	(B)	(C)	(D)	(E)	(F) CxE	(G)	(H) CxG	(I) F + H	(J) 1% x (F + H)	(K) 25% x (I+J)	(L) 12% x (I+J + K)	(M) I + J + K+ L
	4. Perimeter Fence, Lamp Post, Gutter Curves and Parking areas											
	4.1 Elastomeric Primer	6	gal/s	-	-	-	-	-	-	-	-	-
	4.2 Dirt Shield Elastomeric Semi-Gloss	8	tin/s	-	-	-	-	-	-	-	-	-
	4.3 Quick Dry Enamel	5	gal/s	-	-	-	-	-	-	-	-	-
	4.4 Silver Aluminum	2	gal/s	-	-	-	-	-	-	-	-	-
	4.5 Metal Primer	2	gal/s	-	-	-	-	-	-	-	-	-
	4.6 Reflectorized Traffic Paint	5	gal/s	-	-	-	-	-	-	-	-	-
	5. Parapet Wal Ledgesl and Canopy											
	5.1 Waterproofing Multi-Seal	5	tin/s	-	-	-	-	-	-	-	-	-
	5.2 Waterproofing Membrane	7	gal/s	-	-	-	-	-	-	-	-	-
	6. Concrete Putty, Glazing Putty, Wood Putty, Patching Compound, Concrete Epoxy A&B Multi-Purpose epoxy A&B, Rust Converter	1	lot	-	-	-	-	-	-	-	-	-
	7. Miscellaneous Items (paint roller,paint brush, sand paper, putty knife, masking tape and other incidental materials that need to perform the work)	1	lot	-	-	-	-	-	-	-	-	-
	TOTAL COST - PAINTING WORKS											-
											TOTAL PROJECT COST	-

Submitted By: _____
Company Name

Prepared By: _____
Company Representative
(Signature Over Printed Name)

Address: _____

Telephone No.: _____

GENERAL CONDITIONS:

- 1 For uniformity and evaluation purposes, a bidder shall adhere to the herein prescribe format of BOQ, specifically in the formula for computation, given quality and inclusive . pay items. Any deviation from the format shall be a ground for disqualification of bid.
- 2 Bidders are not allowed to include any pay items that were not indicated in the hard copy of BOQ. In instances where necessary work/items are inadvertently left out in BOQ Form, a bidder should make a written query to the Bids and Awards Committee so that the same shall be addressed in the Bid Bulletin which will be issued to all . participating bidders.
- 3 Prospective bidders are required to conduct site inspection to determine all incidental, materials and activities that are necessary to be furnished and executed to complete the project. Examine the site premises and all condition apparent and visible therein. Consider all such conditions that may affect work. Measure every existing work at site. Verify all given dimensions and deviations in the plans/drawings and Bill of Quantities. It shall be understood that the work covers all exposed external surfaces regardless . of measurements made.