



SOCIAL SECURITY SYSTEM
Branch Expansion and Management Services Department

PROJECT : **REPLACEMENT AND REPAIR OF SSS PASAY-CCP COMPLEX SIGNAGE**
SUBJECT : SCOPE OF WORKS
DATE : 10 August 2022

SCOPE OF WORKS AND MATERIAL SPECIFICATIONS

The work contemplated under this contract shall consist of furnishing of all materials, labor, tools and equipment, permits including satisfactory performance of all work necessary for the complete execution of all the work as shown on the plans, specifications and other contract documents. The following are the scope of work:

1. BRANCH SIGNAGES

- a. Replacement of Acrylic Built-up Letters from PASAY-ROXAS BRANCH to PASAY-CCP COMPLEX BRANCH


PARTICULARS	DESCRIPTION	REMARKS
MATERIAL SPECIFICATIONS		
1. Storefront Horizontal and Vertical Signage	- 4mm thk. Aluminum Composite Panel - Aluminum sub-framing and accessories - 50mm thk. built-up embossed Acrylic Logo Color: white - 50mm thk. built-up embossed Acrylic Letters Color: white Font: Eramis Demi ITC - LED lighting including power supply, switches, conduits, outlets and necessary accessories	- Size: refer to BOQ and Drawing Plans

Leave premises clean, neat and orderly. Remove all stains, spots, blemishes, soil dirt from all finished work. Remove all excess materials, soil, used containers, tools, equipment and supplies out of the SSS premises during the progress of work and upon completion of work.

Prepared by:


Regine M. Ignacio
Sr. Engineer, BEMSD

Checked and Reviewed by:


Hanz Howard Roy F. Sabordo, Jr.
Concurrent Acting Head – Technical Section

Noted by:


Mary Goy B. Galang
Concurrent Acting Head, BESMD